



ST. CLAIR CATHOLIC
DISTRICT SCHOOL BOARD
Lighting the Way ~ Rejoicing in Our Journey

ADDENDUM # 001

St. Clair Catholic District School Board

**Our Lady of Fatima
545 Baldoon Rd
Chatham, ON**

**General Renovations and Addition for Mechanical
Equipment
Phase III**

Project No. 619-CP1902

Prepared by:

Wilson Diaz Architects Inc.
280 Queens Ave, Suite 1Q
London, Ontario
N6B 1X3

April 6th. 2019

This addendum forms part of the Contract Bid Documents and amends the original drawings and specifications issued for Bid on February 19th. 2019.

TABLE OF CONTENTS

ADDENDUM # 1 (Including cover)	5 Page(s)
Attachments:	
Section 08 11 00 – Aluminum Doors and Frames	13 Page(s)
M&E ADDENDUM #1:	24 Page(s)

TOTAL PAGE COUNT FOR THIS ADDENDUM	42 Page(s)
------------------------------------	------------

PART A – GENERAL

1.1 MANDATORY SITE VISIT REVIEW/QUESTIONS

At the beginning of the meeting, the SCCDSB and WDAI emphasized that the Site Visit is a MANDATORY visit. The Board therefore, will only receive offers from the contractors listed below:

Our Lady of Fatima Catholic School - Mandatory Site Visit List

Company	Name of Representative	Email
K&L Construction	Kevin Johnson	estimating@kandlconstruction.com
Elgin Contracting	Brad Rule	info@elgincontracting.com
D Grant Construction	Adam Wilken	swillis@dgrantconstruction.com
Vince Ferro Construction LTD.	Brian Miles	vferro@mnsi.net
Accuratus Design Build	Koohyar Tahnasebpour	justin@accuratusdesignbuild.com
Elmara	Colin Stass	colinst@elmira.com
Norlon Construction	Rick Fagnoli	norlon@norlon.ca
Elric Contractors	David Pollard	elriccontractor@gmail.com
Alliance	Don Dykeman	dond.alliance@gmail.com
Bill Hoekstra General Contracting	Bill Hoekstra	info@bh-gc.com
Aveiro Constructors	Christy Aveiro	estimating@aveiroconstructors.com
Intrepid Construction	Paul Kulin	paulk@intrepidgeneral.ca
TCI Construction	Naveenchander Arni	Estimator@tciwindsor.com

Project Scope Discussion:

- Renovation to select areas in school ceiling areas to install new mechanical equipment and sprinkler systems, new lighting and electrical in classrooms, hallways and school entrances.
- New mechanical room addition @ rear of school to house fluid cooler unit.
- New exterior wall assembly consisting of new membrane, spray foam insulation, Limestone base, brick masonry and corrugated metal siding finishes to the extent shown on drawings.
- New exit corridor through middle of the school, and close in of existing corridor.
- Parapets will be bumped up to new height.
- Site and utility works as shown on drawings
- Separate price for new exterior pole lighting.

Please consult drawings and specifications for full extent of work to be completed in this phase.

Questions, comments and discussion from General Contractors:

a. Question:

Who is responsible for submitting and paying for the building permit?

Answer:

The architect has submitted for building permit. Refer to bid documents for payment responsibility.

b. Question:

What will the working hours be once school resumes?

Answer:

This project is to be completed over 2-month period, mobilizing to the site June 28th. and ending August 28th. Refer to Instructions to Bidders Section 1.11 Timing of Project for further details. Any subsequent outstanding work will be done afterhours (evenings and weekends). Work in the mechanical room may continue during regular working hours provided that all activities are within the mechanical room area.

c. Question:

Please clarify the reuse of ceiling tile and track in the classrooms?

Answer:

The classrooms, upon completion of all above ceiling work will be completed with new track and new tile. During demolition, tile is to be carefully removed and stored to later be reinstalled in the corridor ceilings.

d. Question:

What areas will receive new finishes?

Answer:

New finishes are noted on drawings Room 142, 144, 144A and new corridor CR7.

e. Question:

There are, I believe, three new distribution panels required, but I do not see any panel schedules in the prints. Will they be issued?

Answer:

Refer to Mechanical and Electrical Addendum as part of this document.

f. Question:

Also, as a point of clarification, are the classroom modules supplied and populated by others, and installed and wired by division 16 (electrical contractor)?

Answer:

The classroom modules are supplied and installed by the contractor (millwork subcontractor). All devices and wiring is coordinated, supplied and installed by Division 16. Refer to cash allowances for additional information and instructions.

PART B – SPECIFICATIONS

1. Refer to Bid Form – Page 3

Add under Division 8 – Doors and Windows

Section 08 11 00 – Aluminum Doors and Frames

13 Pages

PART C – ARCHITECTURAL DRAWINGS

1. Refer to Drawing A402 – Details 11 and 12.
Revise notes to read “New door and frame”
2. Replace Drawing A010 with attached drawing A010 revised.
3. Replace Drawing A100 with attached drawing A100 revised.
4. Replace Drawing A150 with attached drawing A150 revised.

ARCHITECTURAL SKETCHES

RESERVED

PART D – STRUCTURAL DRAWINGS

RESERVED


PART E – MECHANICAL / ELECTRICAL DRAWINGS

1. Refer to attached Addendum No. 1 issued by Chorley + Bisset
Mechanical Specifications & Electrical Specifications **24 Page(s)**
Reissued Drawings M710 and E100, 2 Page(s) included in above page count


PART F – CIVIL AND SITE WORK DRAWINGS

RESERVED


END OF ADDENDUM # 001



1 LIFE SAFETY PLAN
 A010 1:300




3 TYPICAL LIGHT STANDARD DETAIL
 A010 1:20




4 SITE PLAN
 A010 1:300

KEY PLAN



NOTES

LEGEND




Date	Description	No.
03/06/2019	ADDENDUM 001	5
03/05/2019	ISSUED FOR ADDENDUM 001	5
02/25/2019	ISSUED FOR PERMIT	4
02/19/2019	ISSUED FOR TENDER	3
12/11/2018	ISSUED FOR REVIEW	2
10/18/2018	ISSUED FOR REVIEW	1

PROJECT TITLE
OUR LADY OF FATIMA PHASE 3 RENEWAL

DRAWING TITLE
LIFE SAFETY PLAN SITE PLAN

DATE	DRAWN BY	DRAWING No.
10/18/2018	MFPJ	A010
SCALE	CHECKED BY	
As indicated	RW	
PROJECT No.	1819	

KEY PLAN



TRUE NORTH CONSTRUCTION NORTH

NOTES

LEGEND


SYMBOL	DESCRIPTION
1	DEMOLITION NOTE REFERENCE NUMBER
[Hatched Box]	AREA OF WORK N.I.C.
[Dashed Box]	ACT CEILING TILE TO BE REMOVED
[Dotted Box]	PORTION OF EXISTING WALLS TO BE REMOVED
[Cross-hatched Box]	EXTERIOR MASONRY & INSULATION TO BE REMOVED
[Diagonal Lines]	EXISTING CONC. BLOCK TO REMAIN
[Stippled Box]	AREA OF CONCRETE FLOOR TO BE REMOVED FOR PLUMBING
[Solid Box]	EXISTING DOOR & FRAME TO REMAIN
[Dashed Box]	EXISTING DOOR & FRAME TO BE REMOVED

Date	Description	No.
03/06/2019	ADDENDUM 001	5
03/06/2019	ISSUED FOR ADDENDUM 001	5
02/25/2019	ISSUED FOR PERMIT	4
02/19/2019	ISSUED FOR TENDER	3
12/11/2018	ISSUED FOR REVIEW	2
10/18/2018	ISSUED FOR REVIEW	1

PROJECT TITLE
OUR LADY OF FATIMA PHASE 3 RENEWAL

DRAWING TITLE
DEMOLITION PLAN

DATE 10/18/2018	DRAWN BY MFPU	DRAWING No. AD100
SCALE As indicated	CHECKED BY RW	
PROJECT No. 1819		



- DEMOLITION NOTES:**
- REMOVE EXISTING WALLS AS INDICATED ON THE DRAWINGS. CONSTRUCTION TYPE MAY VARY FROM EXTERIOR MASONRY ON CONCRETE BLOCK BACKUP TO INTERIOR CONCRETE BLOCK AND/OR DRYWALL PARTITIONS. REMOVE MECHANICAL AND ELECTRICAL COMPONENTS / DEVICES (BACK TO SOURCE) ANCHORED TO OR CONCEAL WITHIN WALLS. PROVIDE ALL SHORING AND TEMPORARY SUPPORT REQUIRED TO MAKE EXISTING STRUCTURE SAFE. REFER TO DRAWINGS & SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
 - EXISTING DOOR, AND FRAME IF INDICATED, TO BE REMOVED. BOX, LABEL AND TURN OVER HARDWARE TO OWNER FOR FUTURE USE. WHERE FRAME IS REMOVED PREPARE OPENING TO RECEIVE NEW INFILL OR DOOR AND FRAME. REFER TO NEW CONSTRUCTION PLANS AND ELEVATIONS.
 - EXISTING PLUMBING FIXTURES TO BE REMOVED. REMOVE ALL EQUIPMENT, CAP & REMOVE SINKS, DRAINS, AND HARDWARE. REFER TO MECHANICAL AND ELECTRICAL FOR ADDITIONAL REQUIREMENTS. ONLY RETAIN FIXTURES FOR OWNERS' USE OR REUSE IN NEW CONSTRUCTION WHERE SPECIFICALLY NOTED. REPAIR AND MAKE GOOD ALL EXPOSED SURFACES.
 - REMOVE ALL CEILING TREATMENTS. TAKE CARE TO NOT DAMAGE LAY-IN ACOUSTIC TILE. SAFELY STORE TILE FOR LATER REUSE IN NEW LAY GRID. REMOVE & DISCARD ALL OTHER CEILING TREATMENTS SUCH AS GYPSUM BOARD, METAL FRAMING, SUPPORT HANGERS AND OTHER FIXTURES UNLESS NOTED OTHERWISE.
 - REMOVE EXISTING L.E.D. LIGHT FIXTURES. TURN OVER EXISTING LED BULB TO OWNER.
 - EXISTING FLOOR FINISHES AND WALL BASE TO BE REMOVED INCLUDING ALL ADHESIVES AND MORTAR DOWN TO EXISTING CONCRETE SLAB AND WALL BACKING BY MEANS OF GRINDING. PREPARE FLOOR SURFACE LEVEL TO WITHIN SPECIFIED TOLERANCES AND MAKE READY FOR NEW FINISHES. PROVIDE ANY AND ALL REMEDIAL WORK TO WALL BACKING WHERE BASE HAS BEEN REMOVED. REFER TO NEW CONSTRUCTION PLANS AND ELEVATIONS.
 - REMOVE & DISPOSE OF EXISTING EXTERIOR BRICK AND RIGID INSULATION BACK TO EXISTING CONC. BLOCK. WALL CONC. BLOCK STRUCTURE TO REMAIN. MAKE READY FOR NEW MASONRY.
 - REMOVE AND DISPOSE OF EXISTING WINDOW. PREPARE OPENING TO BE FILLED WITH WALL CONSTRUCTION TO MATCH EXISTING.
 - CUT OPENING IN EXISTING CMU WALL FOR NEW DOOR OPENING. COORDINATE ROUGH OPENING SIZE WITH ARCHITECTURAL DRAWINGS AND DOOR SCHEDULE.

- GENERAL NOTES:**
- REMOVE ALL WIRING FROM ELECTRICAL DEVICES THAT WILL BE REMOVED AND ALL REDUNDANT CONDUIT BACK TO NEAREST JUNCTION BOX THAT WILL REMAIN, AND MAKE SAFE. INSTALL METAL COVER PLATES OVER EXPOSED OPENINGS AND ELECTRICAL BOXES. REFER TO ELECTRICAL FOR ADDITIONAL REQUIREMENTS.
 - MAKE GOOD ALL AREAS AFFECTED BY REMOVALS - FLUSH TO ADJACENT SURFACE AND MATCH TO EXISTING FINISH.
 - DISPOSE OF ALL DESIGNATED SUBSTANCES TO THE REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 - ALL PIPING THAT IS TO BE REMOVED OR ABANDONED IS TO BE REMOVED BACK TO THE NEAREST JUNCTION AND CAPPED. REFER TO MECHANICAL FOR ADDITIONAL REQUIREMENTS.
 - NOTE ALL EXISTING ITEMS MAY NOT BE SHOWN ON THESE DRAWINGS. A CAREFUL REVIEW OF THE SITE IS REQUIRED TO DETERMINE THE FULL EXTENT OF THE WORK SHOWN. CONTACT ARCHITECT PRIOR TO BID CLOSE TO CONFIRM.
 - THE ARCHITECTURAL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL PROJECT MANUALS, STRUCTURAL, CIVIL, MECHANICAL AND ELECTRICAL DRAWINGS. IN CASE OF DIFFERENCES BETWEEN CONSULTANTS' DOCUMENTS WITH RESPECT TO QUANTITY, SIZES OR SCOPE, THE GREATER SHALL APPLY.
 - PROVIDE PROTECTION FOR ALL FINISHES OR SERVICES TO REMAIN.
 - ALL WINDOWS FALLING WITHIN THE DEMOLITION AREA ARE TO HAVE THEIR COVERINGS, FITTINGS, AND MOUNTING HARDWARE REMOVED & RETURNED TO THE OWNER.
 - DEMOLITION NOTE REFERENCE NUMBERS, WHERE LOCATED ADJACENT TO A ROOM NAME/NUMBER APPLY TO THE ENTIRETY OF THE ROOM.
 - GENERAL CONTRACTOR IS TO ALLOW FOR THE SUPPLY AND INSTALLATION OF LOOSE LINTELS AS REQUIRED WHERE NEW OPENINGS ARE BEING CREATED OR WIDENED. REFER TO THE LOOSE LINTEL SCHEDULE PROVIDED ON THE DRAWINGS, OR PROVIDE ENGINEERING WHERE THERE ARE NO STRUCTURAL DRAWINGS OR SCHEDULE.
 - GENERAL CONTRACTOR IS REQUIRED TO REMOVE ALL REMAINING ADHESIVES ON WALLS WHERE COMMUNICATION BOARDS WERE REMOVED UNLESS BEING COVERED WITH NEW BOARDS. TYPICAL FOR ALL ROOMS AFFECTED BY WORK.

1
AD100
DEMOLITION PLAN PH 3
1 : 150

Our Lady of Fatima
Phase 3 Renewal
Chatham, Ontario
St. Clair Catholic District School Board

Chorley + Bisset Ltd.
Consulting Engineers
London, Ontario

6 March 2019

Page 1 of 4

Plus Revision Drawing MR-1 to MR-4, ER-1 to ER-3
Reissued Drawing M701, E100
Panel Schedules
Section 16705 - Security and Access Control

ADDENDUM NO. 1

Make the following amendments and additions to the Drawings and Specifications, and include this cost in the Contract Price.

1. MECHANICAL SPECIFICATIONS

1. Section 15600 - Liquid Heat Transfer

1. Clause 2.22.15: Add "Greenheck" to the list of equals.

2. Section 15900 - Controls

1. Insert Clause 3.21 and revise subsequent numbering accordingly:

3.21 EXTERIOR LIGHTING CONTROL AND MONITORING

- 3.21.1 Provide an outdoor light level sensor and relays for control of lighting room controllers provided by Division 16. Implement a time of day schedule to override sensor operation and shut off lights during the day. Locate outdoor light level sensor on North side of building.
- 3.21.2 Exterior Building Mounted Lighting: To operate dusk-to-dawn with a time of day schedule override. Refer to electrical drawings for room controller location.
- 3.21.3 Parking Lot Lighting: To operate to operate from dusk to dawn, with a time of day schedule override with low/high step dimming control. Enable high output from dusk until 12:00 a.m. Enable low output from 12:00 a.m. to 6:00 a.m. and enable high output from 6:00 a.m. to dawn. Refer to electrical drawings for room controller locations.

2. MECHANICAL DRAWINGS

1. Drawing M101

1. Refer to revision drawing MR-1, attached.

2. Drawing M102

1. Revise section 1 marker to indicate from drawing M601 and drawn on drawing M102.

3. Drawing M201

1. Refer to revision drawing MR-2, attached.

4. Drawing M301

1. Refer to revision drawing MR-3, attached.
2. Refer to revision drawing MR-4, attached.

5. Drawing M501

1. Delete all fire dampers in transfer ducts between corridors and adjacent rooms, excluding fire dampers between room 144 and corridor.
2. Revise return duct size for of heat pump serving room 128 to 550x250.
3. Revise return duct size for of heat pump serving room 114 to 450x250.
4. Revise diffuser tag of diffuser in room 144A to SD-1 and size of ductwork to 250x150.
5. Revise diffuser tag of diffuser in room 144 to SD-2.

6. Drawing M701

1. Refer to reissued drawing, attached.

7. Drawing M703

1. Add note 2, "Generally, all supply air ductwork and diffusers from the existing rooftop unit is to be removed."

3. ELECTRICAL SPECIFICATIONS

1. Section 16400

1. Add Panel Schedules attached in their entirety.

2. Section 16705

1. Add Section 16705 - Security and Access Control attached in its entirety.

4. ELECTRICAL DRAWINGS

1. Drawing E100

1. Reissue Drawing E100 attached in its entirety.

2. Drawing E200

1. Add emergency light remote head to IT (Room 144A). Connect to emergency battery pack in Cust (Room 144).
2. Connect Luminaire Type B2 in IT (Room 144A) to circuit A-2.
3. Provide Room Controller with dimming and input module above Panel A for control of site lighting fixtures connected to circuit A-53. Site lighting to be controlled by the BAS.
4. Provide Room Controller with dimming and input module above Panel E for control of site lighting fixtures connect to circuit E-55. Site lighting to be controlled by the BAS.
5. Complete electrical revisions as indicated on Revision Drawing ER-1 and ER-2 attached.

3. Drawing E300

1. Add Ground Bar at data rack in IT (Room 144A). Refer to Grounding Bonding Arrangement detail on Drawing E500.
2. Connect door operator in Corridor CR-7 to circuit C-53.
3. Revise Note 2 and Note 4 on **Mechanical Room Detail** to read: "Provide relay and contactor for existing building mounted site lighting. Relay to be controlled by the BAS. Rework wiring and conduit serving building mounted site lighting to new Panel 'C'".

4. Drawing E400

1. Revise Note 4 to read: "...Unless otherwise noted, completely remove and reinstall all ceiling mounted lighting and fire alarm devices within the outlined area as required for sprinkler piping installation. Coordinate with sprinkler contractor."
2. Remove site lighting relays, contactors and time clocks made redundant by this phase. Remove all associated wiring and conduit back to source.
3. Complete electrical revisions as indicated on Revision Drawing ER-3 attached.

5. Drawing E401

1. Revise Note 1 to read: "...purposes only. Unless otherwise noted, completely remove and reinstall all ceiling mounted power and systems devices within the outlined area as required for sprinkler piping installation. Coordinate with sprinkler contractor."

END OF ADDENDUM NO. 1

FILE NAME: 8586DMR1.DWG
 DATE SAVED: 04-Mar-2019 1:37 PM
 DATE PLOTTED: 05-Mar-2019 10:39 AM



Chorley + Bisset
 CONSULTING ENGINEERS
 chorley.com

369 YORK ST., SUITE 2B 250 CITY CENTRE AVE., SUITE 403
 LONDON ON, N6B 3R4 OTTAWA ON, K1R 6K7


VIBRATION ISOLATORS

DRAWING REFERENCE	MANUFACTURER	MODEL	STATIC DEFLECTION (MM)	REMARKS
FC-502	VIBRO	SCSR-2AH	50	MINIMUM SIX UNITS - HOT DIPPED GALVANIZED 150mm THICK CONCRETE INERTIA BASE (USE VIBRO ENUN2 FLEX CONNECTORS WITH CONTROL RODS) USE FOR PIPING SERVICE CP-302A/B - MINIMUM FIRST 3 HANGER RODS
CP-302A/B	VIBRO	CIB/SIPS/SFS	25	
PIPING	VIBRO	SHB	-	

REVISION TO DRAWING M101

Title	VIBRATION ISOLATORS SHCEDULES REVISION
Project	OUR LADY OF FATIMA PHASE 3 RENEWAL THAMES VALLEY DISTRICT SCHOOL BOARD

Drawn	BMD	Date	03/01/2019
Checked	JDF	Project No.	8586
Approved	JDF	Drawing No.	MR-1
Scale	1:100		



GROUND FLOOR PLAN 
PLUMBING
 SCALE: 1:100

REVISION TO DRAWING M201


FILE NAME: 8586DMR-2.DWG
 DATE SAVED: 04-Mar-2019 1:37 PM
 DATE PLOTTED: 05-Mar-2019 10:40 AM



Chorley + Bisset
 CONSULTING ENGINEERS
 chorley.com

369 YORK ST., SUITE 2B 250 CITY CENTRE AVE., SUITE 403
 LONDON ON, N6B 3R4 OTTAWA ON, K1R 6K7

Title	GROUND FLOOR PLAN PLUMBING REVISION		Drawn	BMD	Date	03/01/2019
			Checked	JDF	Project No.	8586
Project	OUR LADY OF FATIMA PHASE 3 RENEWAL THAMES VALLEY DISTRICT SCHOOL BOARD		Approved	JDF	Drawing No.	MR-2
			Scale			



DETAIL
 SCALE: 1:50
 A
 M301 M301

- NOTES:**
- CONNECT TO EXISTING FLANGE.

REVISION TO DRAWING M301

FILE NAME: 8586DMR-3.DWG
 DATE SAVED: 05-Mar-2019 10:40 AM
 DATE PLOTTED: 05-Mar-2019 10:40 AM




369 YORK ST., SUITE 2B LONDON ON, N6B 3R4
 250 CITY CENTRE AVE., SUITE 403 OTTAWA ON, K1R 6K7

Title	FIRE PROTECTION DETAIL REVISION
Project	OUR LADY OF FATIMA PHASE 3 RENEWAL THAMES VALLEY DISTRICT SCHOOL BOARD

Drawn	BMD	Date	03/01/2019
Checked	JDF	Project No.	8586
Approved	JDF	Drawing No.	MR-3
Scale			

ZONE L1
NORTH

MECH
ROOM
ZONE



GROUND FLOOR PLAN
FIRE PROTECTION



SCALE: 1:100

REVISION TO DRAWING M301


FILE NAME: 8586DMR-4.DWG
DATE SAVED: 05-Mar-2019 11:25 AM
DATE PLOTTED: 05-Mar-2019 11:26 AM



Chorley + Bisset
CONSULTING ENGINEERS
chorley.com

369 YORK ST., SUITE 2B 250 CITY CENTRE AVE., SUITE 403
LONDON ON, N6B 3R4 OTTAWA ON, K1R 6K7

Title	GROUND FLOOR PLAN FIRE PROTECTION REVISION		Drawn	BMD	Date	03/01/2019
	Project	OUR LADY OF FATIMA PHASE 3 RENEWAL THAMES VALLEY DISTRICT SCHOOL BOARD	Checked	JDF	Project No. 8586	
Approved			JDF	Drawing No.		
Scale				MR-4		



**GROUND FLOOR PLAN - LIGHTING
AND FIRE ALARM**



SCALE: 1:100

REVISIONS TO DRAWING E200


FILE NAME: 8586RE001.DWG
DATE SAVED: 05-Mar-2019 4:45 PM
DATE PLOTTED: 06-Mar-2019 10:52 AM



369 YORK ST., SUITE 2B LONDON ON, N6B 3R4
250 CITY CENTRE AVE., SUITE 403 OTTAWA ON, K1R 6K7

Title	GROUND FLOOR PLAN - LIGHTING AND FIRE ALARM REVISIONS
Project	OUR LADY OF FATIMAT PHASE 3 RENEWAL ST. CLAIR CATHOLIC DISTRICT SCHOOL BOARD CHATHAM, ONTARIO

Drawn	ZJRL	Date	MAR 2019
Checked	ZJRL	Project No.	8586
Approved	RDZ	Drawing No.	ER-1
Scale	AS NOTED		



**GROUND FLOOR PLAN - LIGHTING
AND FIRE ALARM**

SCALE: 1:100



REVISIONS TO DRAWING E200

FILE NAME: 8586RE002.DWG
DATE SAVED: 05-Mar-2019 4:45 PM
DATE PLOTTED: 06-Mar-2019 10:53 AM




Chorley + Bisset
CONSULTING ENGINEERS
chorley.com

369 YORK ST., SUITE 2B 250 CITY CENTRE AVE., SUITE 403
LONDON ON, N6B 3R4 OTTAWA ON, K1R 6K7

Title	GROUND FLOOR PLAN - LIGHTING AND FIRE ALARM REVISIONS
Project	OUR LADY OF FATIMAT PHASE 3 RENEWAL ST. CLAIR CATHOLIC DISTRICT SCHOOL BOARD CHATHAM, ONTARIO

Drawn	ZJRL
Checked	ZJRL
Approved	RDZ
Scale	AS NOTED

Date	MAR 2019
Project No.	8586
Drawing No.	ER-2



GROUND FLOOR PLAN - LIGHTING
AND FIRE ALARM DEMOLITION



SCALE: 1:100

REVISIONS TO DRAWING E400

FILE NAME: 8586RE003.DWG
 DATE SAVED: 05-Mar-2019 4:44 PM
 DATE PLOTTED: 06-Mar-2019 10:53 AM



Chorley + Bisset
 CONSULTING ENGINEERS
 chorley.com


369 YORK ST., SUITE 2B 250 CITY CENTRE AVE., SUITE 403
 LONDON ON, N6B 3R4 OTTAWA ON, K1R 6K7

Title	GROUND FLOOR PLAN - LIGHTING AND FIRE ALARM DEMOLITION REVISIONS
Project	OUR LADY OF FATIMAT PHASE 3 RENEWAL ST. CLAIR CATHOLIC DISTRICT SCHOOL BOARD CHATHAM, ONTARIO

Drawn	ZJRL
Checked	ZJRL
Approved	RDZ
Scale	AS NOTED


Date	MAR 2019
Project No.	8586
Drawing No.	ER-3

DO NOT SCALE THE DRAWINGS. ALL MEASUREMENTS ARE TO BE CHECKED AND VERIFIED ON SITE BY THE CONTRACTOR. ANY DISCREPANCIES ARE TO BE REPORTED TO THE CONSULTANT BEFORE PROCEEDING WITH THE WORK.
COPYRIGHT © ALL RIGHTS RESERVED. ALL DRAWINGS AND RELATED DOCUMENTS ARE THE COPYRIGHT OF THE CONSULTANT AND MUST BE RETURNED UPON REQUEST OR AT THE COMPLETION OF THE WORK. REPRODUCTION OF THESE DRAWINGS OR RELATED DOCUMENTS IN PART OR IN WHOLE, BY ELECTRONIC OR MECHANICAL MEANS, IS FORBIDDEN BY LAW WITHOUT THE PRIOR WRITTEN PERMISSION OF THE CONSULTANT.




PART GROUND FLOOR PLAN
PLUMBING DEMOLITION
SCALE: 1/100


NOTES:
1. SEE PLUMBING DEMOLITION SCHEMATIC FOR MECHANICAL ROOM DEMOLITION.
2. REMOVE DOMESTIC WATER AND SANITARY PIPING. CAP IN WALL AND BELOW FLOOR.



DOMESTIC HOT WATER SYSTEM SCHEMATIC - DEMOLITION
N.T.S.




KEY PLAN



NOTES

Date	Description	No.
03/01/2019	ISSUED PER ADDENDUM	3
02/20/2019	ISSUED FOR TENDER/PERMIT	2
12/11/2018	ISSUED FOR REVIEW	1



PROJECT TITLE
OUR LADY OF FATIMA PHASE 3 RENEWAL

DRAWING TITLE
GROUND FLOOR PLAN DEMOLITION PLUMBING

DATE 02/20/2019	DRAWN BY BMD	DRAWING NO. M701
SCALE AS NOTED	CHECKED BY JDF	
PROJECT NO. 8586		

PROJ. NAME: OUR LADY OF FATIMA PHASE 2 RENEWAL
PROJ. NO : 8391

PANEL ID: HPA
MAINS: 225A
VOLTAGE: 208/120V, 3Ø, 4W
MOUNTING: FLUSH
NO OF CKT: 72

LOCATION: CORRIDOR
FED FROM: MAIN DISTRIBUTION BOARD 'DP1'
COMMENTS:
 NEW HEAT PUMP PANEL

CKT	BRKR	DESCRIPTION	WATTS	CKT	BRKR	DESCRIPTION	WATTS
1	15	HP-403 IN CR1-5	2350	2	20	HP-405 IN CR1-5	5155
3	2P			4			
5	20	HP-405 IN CR1-5	5155	6	3P	HP-405 IN CR1-5	5155
7				8	20		
9	3P			10			
11	20	HP-406 IN CR1-5	6323	12	3P	HP-405 IN CR1-5	5155
13				14	20		
15	3P			16			
17	20	HP-405 IN CR1-5	5155	18	3P	HP-405 IN CR1-5	5155
19				20	20		
21	3P	HP-401 IN CR1-7	1048	22		HP-405 IN CR1-5	6323
23	15			24	3P		
25	2P	HP-401 IN CR1-7	1048	26	20	HP-405 IN CR1-3	5155
27	15			28	3P		
29	2P			30			
31	20	HP-406 IN CR1-4	6323	32	20	HP-405 IN CR1-4	5155
33				34			
35	3P			36	3P		
37	20	HP-405 IN CR1-4	5155	38			
39				40			
41	3P			42			
43				44			
45				46			
47				48			
49				50			
51				52			
53				54			
55				56			
57				58			
59				60			
61	15	SPARE		62	15	SPARE	
63				64			
65	3P	SPARE		66	3P	SPARE	
67	20			68	20		
69				70			
71	3P			72	3P		

PROJ. NAME: OUR LADY OF FATIMA PHASE 2 RENEWAL
PROJ. NO : 8391

PANEL ID: A
MAINS: 225A
VOLTAGE: 208/120V, 3Ø, 4W
MOUNTING: FLUSH
NO OF CKT: 72

LOCATION: CORRIDOR
FED FROM: MAIN DISTRIBUTION BOARD 'DP1'
COMMENTS:
 NEW PANEL TO REPLACE EXISTING

CKT	BRKR	DESCRIPTION	WATTS	CKT	BRKR	DESCRIPTION	WATTS
1	20	RM 134, 136, 138 LTG		2	20	NORTH CORRIDOR LTG	
3	20	NORTH CLASSROOM LTG		4			
5				6			
7	20	EXISTING CIRCUIT		8	20	EXISTING CIRCUIT	
9	20	EXISTING CIRCUIT		10	20	EXISTING CIRCUIT	
11	20	EXISTING CIRCUIT		12	20	EXISTING CIRCUIT	
13	20	EXISTING CIRCUIT		14	20	EXISTING CIRCUIT	
15	20	EXISTING CIRCUIT		16	20	EXISTING CIRCUIT	
17	20	EXISTING CIRCUIT		18	20	EXISTING CIRCUIT	
19	20	EXISTING CIRCUIT		20	20	EXISTING CIRCUIT	
21	15	EXISTING CIRCUIT		22	15	EXISTING CIRCUIT	
23	15	EXISTING CIRCUIT		24	15	EXISTING CIRCUIT	
25	15	EXISTING CIRCUIT		26	15	EXISTING CIRCUIT	
27	15	EXISTING CIRCUIT		28	15	EXISTING CIRCUIT	
29	15	EXISTING CIRCUIT		30	15	EXISTING CIRCUIT	
31	15	EXISTING CIRCUIT		32	15	EXISTING CIRCUIT	
33	15	EXISTING CIRCUIT		34	15	EXISTING CIRCUIT	
35	15	EXISTING CIRCUIT		36	15	EXISTING CIRCUIT	
37				38	15	EXISTING CIRCUIT	
39				40	20	EXISTING CIRCUIT	
41	20	RTU-101 REC		42	20	EXISTING CIRCUIT	
43	20	RM 144,144A REC		44	15	EXISTING CIRCUIT	
45				46	20	RM 130 REC	
47				48	20	RM 128 REC	
49				50	20	RM 126 REC	
51				52	20	RM 124 REC	
53	20	WEST SITE LTG		54	20	RM 122 REC	
55				56	20	RM 134 REC	
57				58	20	RM 136 REC	
59				60	20	RM 138 REC	
61				62			
63				64			
65	15	SPARE		66	15	SPARE	
67	15	SPARE		68	15	SPARE	
69	20	SPARE		70	20	SPARE	
71	20	SPARE		72	20	SPARE	

PROJ. NAME: OUR LADY OF FATIMA PHASE 2 RENEWAL
PROJ. NO : 8391

PANEL ID: C
MAINS: 225A
VOLTAGE: 208/120V, 3Ø, 4W
MOUNTING: SURFACE
NO OF CKT: 72

LOCATION: MECHANICAL ROOM 150B
FED FROM: MAIN DISTRIBUTION BOARD 'DP1'
COMMENTS:
 NEW PANEL TO REPLACE PANEL 'C', PANEL 'PL' AND
 PANEL 'F'

CKT	BRKR	DESCRIPTION	WATTS	CKT	BRKR	DESCRIPTION	WATTS
1	20	ELEC/MECH ROOM LTG		2	20	EXISTING PANEL 'F' LOAD	
3	15	EXISTING PANEL 'F' LOAD		4	20	EXISTING PANEL 'F' LOAD	
5	15	EXISTING PANEL 'F' LOAD		6	15	EXISTING PANEL 'C' LOAD	
7	15	EXISTING PANEL 'F' LOAD		8	15	EXISTING PANEL 'C' LOAD	
9	15	EXISTING PANEL 'F' LOAD		10	15	EXISTING PANEL 'C' LOAD	
11	15	EXISTING PANEL 'F' LOAD		12	15	EXISTING PANEL 'C' LOAD	
13	15	EXISTING PANEL 'F' LOAD		14	15	EXISTING PANEL 'C' LOAD	
15	20	EXISTING PANEL 'C' LOAD		16	15	EXISTING PANEL 'C' LOAD	
17	20	EXISTING PANEL 'C' LOAD		18	15	EXISTING PANEL 'C' LOAD	
19	20	EXISTING PANEL 'C' LOAD		20	15	EXISTING PANEL 'C' LOAD	
21	20	EXISTING PANEL 'C' LOAD		22	15	EXISTING PANEL 'C' LOAD	
23	20	EXISTING PANEL 'C' LOAD		24	15	EXISTING PANEL 'C' LOAD	
25	20	EXISTING PANEL 'C' LOAD		26	15	EXISTING PANEL 'C' LOAD	
27	20	EXISTING PANEL 'C' LOAD		28	15	EXISTING PANEL 'C' LOAD	
29	20	EXISTING PANEL 'C' LOAD		30	15	EXISTING PANEL 'C' LOAD	
31	20	EXISTING PANEL 'C' LOAD		32	15	EXISTING PANEL 'C' LOAD	
33	20	EXISTING PANEL 'C' LOAD		34	15	EXISTING PANEL 'C' LOAD	
35	20	EXISTING PANEL 'C' LOAD		36			
37	20	EXISTING PANEL 'C' LOAD		38	3P		
39	20	EXISTING PANEL 'C' LOAD		40	50	EXISTING PANEL 'C' LOAD	
41	20	EXISTING PANEL 'C' LOAD		42	2P		
43	20	EXISTING PANEL 'C' LOAD		44	20	EXISTING PANEL 'PL' LOAD	
45	15	EXISTING PANEL 'PL' LOAD		46	20	EXISTING PANEL 'PL' LOAD	
47	15	EXISTING PANEL 'PL' LOAD		48	15	EXISTING PANEL 'C' LOAD	
49	15	CR-7 FORCE FLOW		50	20	EXISTING PANEL 'C' LOAD	
51				52			
53	15	CR-7 DOOR OPERATOR		54			
55				56			
57				58			
59				60			
61				62			
63				64			
65	15	SPARE		66	15	SPARE	
67	15	SPARE		68	15	SPARE	
69	20	SPARE		70	20	SPARE	
71	20	SPARE		72	20	SPARE	

PROJ. NAME: OUR LADY OF FATIMA PHASE 2 RENEWAL
PROJ. NO : 8391

PANEL ID: MA
MAINS: 225A
VOLTAGE: 208/120V, 3Ø, 4W
MOUNTING: SURFACE
NO OF CKT: 72

LOCATION: MECHANICAL ROOM 150
FED FROM: MAIN DISTRIBUTION BOARD 'DP1'
COMMENTS:
 NEW PANEL

CKT	BRKR	DESCRIPTION	WATTS	CKT	BRKR	DESCRIPTION	WATTS
1	15	EXISTING PANEL 'F' LOAD	600	2	15	EXISTING PANEL 'F' LOAD	1080
3	15	EXISTING PANEL 'F' LOAD	600	4	15	EXISTING PANEL 'F' LOAD	1000
5	15	EXISTING PANEL 'F' LOAD	600	6	15	EXISTING PANEL 'F' LOAD	1000
7	15	EXISTING PANEL 'F' LOAD	1080	8	20 GFCI	METERING CABINET REC	300
9	20	EXISTING PANEL 'F' LOAD	1080	10	20	BAS HEADEND REC	1000
11	20	MECHANICAL ROOM REC	300	12	15	UH-420 RM 150B	600
13	40	CP-302B	10000	14	40	CP-302A	10000
15	16						
17	18			3P			
19	15	CP-304A	1419	20	15	CP-304B	1419
21	22						
23	24			3P			
25	15	CP-303A	1419	26	15	CP-303B	1419
27	28						
29	30			3P			
31	15	CP-305A	2675	32	15	CP-305B	2675
33	34						
35	36			3P			
37	15	CP-306	675	38	15	EF-2	675
39	15	FLUID COOLER REC	1000	40			
41				42			
43				44			
45				46			
47				48			
49				50			
51				52			
53				54			
55				56			
57				58			
59				60			
61				62	15	SPARE	
63				64			
65	15	SPARE		66	3P		
67	15	SPARE		68	20	SPARE	
69	20	SPARE		70			
71	20	SPARE		72	3P		

PROJ. NAME: OUR LADY OF FATIMA PHASE 2 RENEWAL
PROJ. NO : 8391

PANEL ID: E
MAINS: 225A
VOLTAGE: 208/120V, 3Ø, 4W
MOUNTING: SURFACE
NO OF CKT: 66

LOCATION: STORAGE ROOM
FED FROM: MAIN DISTRIBUTION BOARD 'DP1'
COMMENTS:
 PROVIDE NEW BREAKERS TO SUIT EXISTING
 SIEMENS PANEL

CKT	BRKR	DESCRIPTION	WATTS	CKT	BRKR	DESCRIPTION	WATTS
1	15	EXISTING CIRCUIT		2	15	EXISTING CIRCUIT	
3	15	EXISTING CIRCUIT		4	15	EXISTING CIRCUIT	
5	15	EXISTING CIRCUIT		6	15	EXISTING CIRCUIT	
7	15	EXISTING CIRCUIT		8	15	EXISTING CIRCUIT	
9	15	EXISTING CIRCUIT		10	15	EXISTING CIRCUIT	
11	15	EXISTING CIRCUIT		12	15	EXISTING CIRCUIT	
13	15	EXISTING CIRCUIT		14	15	EXISTING CIRCUIT	
15	15	EXISTING CIRCUIT		16	15	EXISTING CIRCUIT	
17	15	EXISTING CIRCUIT		18	15	EXISTING CIRCUIT	
19	15	EXISTING CIRCUIT		20	15	EXISTING CIRCUIT	
21	15	EXISTING CIRCUIT		22	15	EXISTING CIRCUIT	
23	20	EXISTING CIRCUIT		24	20	EXISTING CIRCUIT	
25	15	EXISTING CIRCUIT		26	20	EXISTING CIRCUIT	
27	20	EXISTING CIRCUIT		28	15	EXISTING CIRCUIT	
29				30	20	EXISTING CIRCUIT	
31	3P			32	20	EXISTING CIRCUIT	
33	15	EXISTING CIRCUIT		34	15	EXISTING CIRCUIT	
35	15	EXISTING CIRCUIT		36	20	EXISTING CIRCUIT	
37	15	EXISTING CIRCUIT		38	20	EXISTING CIRCUIT	
39	15	EXISTING CIRCUIT		40	15	EXISTING CIRCUIT	
41	15	EXISTING CIRCUIT		42	15	EXISTING CIRCUIT	
43	15	EXISTING CIRCUIT		44	15	EXISTING CIRCUIT	
45	15	EXISTING CIRCUIT		46	15	EXISTING CIRCUIT	
47	15	EXISTING CIRCUIT		48	15	EXISTING CIRCUIT	
49	20	EXISTING CIRCUIT		50	15	EXISTING CIRCUIT	
51	20	EXISTING CIRCUIT		52			
53				54			
55	20	NORTH, EAST SITE LTG		56			
57				58			
59				60			
61				62			
63				64			
65				66			

INDEX - SECTION 16705

PART 1 - GENERAL

Description of Systems.	1.2
General Requirements.....	1.1
Submittals.	1.3

PART 2 - PRODUCTS

Materials.....	2.1
Security System.....	2.2

PART 3 - EXECUTION

Accessories.	3.4
General Installation.	3.1
Security System.....	3.2
Verification and Commissioning.	3.3

THIS PAGE LEFT BLANK

-
- 1 General
- 1.1 **GENERAL REQUIREMENTS**
- 1.1.1 Conform to the requirements of Section 16001, "Electrical General Provisions".
- 1.1.2 Products will comply with the latest edition of the following Standards:
- CAN/ULC-S302-M91, Installation and Classification of Burglar Alarm Systems for Financial and Commercial Premises, Safes and Vaults
CAN/ULC-S303-M91, Local Burglar Alarm Units and Systems
CAN/ULC-S306-03, Intrusion Detection Units
CAN/ULC-S319-05, Electronic Access Control Systems
CAN/ULC-S525-99, Audible Signal Appliances
- 1.2 **DESCRIPTION OF SYSTEMS**
- 1.2.1 **Security System**
- 1.2.1.1 Extend existing hardwired DSC security system including conduits, devices and all necessary components, as recommended by manufacturer.
- 1.2.1.2 Provide door contacts and motion sensors.
- 1.3 **SUBMITTALS**
- 1.3.1 Submit Shop Drawings in accordance with the General Conditions of the Contract and as specified in this Section.
- 1.3.2 Provide a written description of the proposed system configuration augmented with block diagrams identifying the location of all system components and associated cable routings.
- 1.3.3 Provide lists of all off-the-shelf and custom equipment, including equipment quantities.
- 1.3.4 Provide the mechanical, electrical and environmental specifications for all listed equipment and cable.
- 1.3.5 Provide an overview of any equipment installation techniques which may deviate from the standards contained in this Section. Expose all such installation techniques for prior approval by the Consultant.
- 2 Products
- 2.1 **MATERIALS**
- 2.1.1 Use materials specified herein or approved equal.
- 2.1.2 Conductors in inaccessible ceiling spaces and partitions are to be installed in electrical metallic tubing in accordance with Specification Section 16700.
- 2.1.3 Conceal all wiring above finished suspended ceilings, except where otherwise noted.

2.1.4 Outlet boxes are to be code gauge, galvanized steel, of a depth necessary to accommodate the number of wires and the device contained therein.

2.2 SECURITY SYSTEM

2.2.1 Detection Devices

2.2.1.1 Door contacts are to be sleeved to fit flush in door frame. Provide repulsion type magnet contacts, suitable for wide gap 2.22 cm (.875"), SPDT contacts, white finish, type similar to Sentrol 1078 CAQ series.

2.2.1.2 Overhead door contacts are to be mounted to side of the door and track. Provide repulsion type magnet contacts, suitable for wide gaps up to 7 mm (3"), SPST contacts, all aluminum housing, 900 mm (36") stainless steel armoured cable, door and door track mounting hardware, Sentrol 2500 Series with 1092A brackets.

2.2.1.3 Quad element motion detector with digital motion detection (no analog detection) circuitry and shielded from EMI and RFI signals, 12 m x 12 m (40' x 40') range with 110° viewing angle, complete with form C relay and anti-tamper switch. Paradox DG65-C.

2.2.2 Wiring

2.2.3 All wiring to be a minimum 22 gauge four conductor, CMP rated, as per manufacturer's recommendations.

2.2.4 The following manufacturers of the above equipment will be considered equal subject to requirements of Clause "Material and Equipment":

DSC NEO

3 Execution

3.1 GENERAL INSTALLATION

3.1.1 Provide all necessary wiring, conduits, outlet boxes and devices for a complete system. Conceal all wiring.

3.1.2 Install all wiring to manufacturer's recommendations. Conceal all conduit within ceiling spaces, walls or partitions, where possible.

3.1.3 Submit complete detailed wiring diagrams with description of system upon completion as per Section 16100. Provide all required instructional support to permit correct use of system by staff members.

3.1.4 Coordinate with door hardware supplier all requirements for system components, door strikes, concealed door contacts in particular. Coordinate power and electrical parameters with the door hardware supplier.

3.1.5 Included in Base Bid for manufacturers representative to spend four hours on site for training Owner's Staff on the operations, maintenance and setup of the access control system. Notify Consultant seven days in advance of scheduled training.

3.2 SECURITY SYSTEM

3.2.1 Flush-mount door contacts in new doors/frames. Wire and connect each door contact to a separate system alarm zone as indicated.

3.2.2 Do not install detectors and door contacts until all room finishes, door trim and seals have been installed.

3.2.3 Mount entry delay horns in ceiling space above key pad.

3.2.4 Provide all necessary programming with documentation and backup. Provide one installation manual, two programming worksheets, 10 sets of User manuals, and 20 quick reference cards. Provide hardware means of convenient backing up and restoring the system program.

3.2.5 Wire all detection devices using form C contact and end of line resistor to provide full supervision against open circuits. Where provided, wire NC tamper switch in series with end of line resistor to provide trouble at panel if activated.

3.2.6 Operation

3.2.6.1 System Disarming

3.2.6.1.1 Opening a designated entry doors will activate door contacts.

3.2.6.1.2 Audible entry (delay horn) tone will advise the operator that the system is armed and the delay on entry has been activated. The operator has 15 seconds to enter their P.I.N. number to disarm the system.

3.2.6.2 Motion Detectors

3.2.6.2.1 On activation of a motion detector, the system panel will initiate an alarm signal.

3.2.6.2.2 On activation of a motion detector tamper switch, the system panel will initiate a trouble signal.

3.2.6.3 Door Contacts

3.2.6.3.1 Activation of a door contact defined as "instant", the system panel will initiate an alarm signal.

3.2.6.3.2 Activation of a door contact defined as "delay", the entry tone will sound and at the end of the programmed delay time period, the system panel will initiate an alarm signal if the system has not been disarmed.

3.3 VERIFICATION AND COMMISSIONING

3.3.1 Verify system and all connected components operation, and provide written Certificate of Verification.

3.3.2 Notify Owner and Consultant minimum seven days in advance of scheduled verification.

3.3.3 Provide all necessary tools, ladders and equipment.

-
- 3.3.4 Ensure appropriate subcontractors, and manufacturer's representatives and security specialists are present for verification.
- 3.3.5 Visual verification: Objective is to assess quality of installation and assembly and overall appearance to ensure compliance with Contract Documents. Visual inspection to include:
- 3.3.5.1 Sturdiness of equipment fastening.
- 3.3.5.2 Non-existence of installation related damages.
- 3.3.5.3 Compliance of device locations with drawings and reviewed shop drawings.
- 3.3.5.4 Compatibility of equipment installation with physical environment.
- 3.3.5.5 Inclusion of all accessories.
- 3.3.5.6 Device and cabling identification.
- 3.3.5.7 Application and location of ULC approval decals.
- 3.3.6 Technical verification: Purpose to ensure that all systems and devices are properly installed and free of defects and damage. Technical verification includes:
- 3.3.6.1 Measurements of coverage patterns
- 3.3.6.2 Connecting joints and equipment fastening.
- 3.3.6.3 Compliance with manufacturer's specification, product literature and installation instructions.
- 3.3.7 Operational verification: Purpose to ensure that devices and systems' performance meet or exceed established functional requirements. Operational verification includes:
- 3.3.7.1 Operation of each device individually and within its environment.
- 3.3.7.2 Operation of each device in relation with programmable schedule and or/specific functions.
- 3.4 **ACCESSORIES**
- 3.4.1 Turn accessories (reference cards, proximity cards, etc.) over to Owner at end of construction. Provide signed letter from Owner listing items and quantities of accessories confirming receipt, and include in electrical manuals.

END OF SECTION