



ST. CLAIR CATHOLIC
DISTRICT SCHOOL BOARD

Lighting the Way ~ Rejoicing in Our Journey

**REQUEST FOR TENDER
FOR
Lighting Retrofit Tender
St. Clair Catholic District School Board
Multiple School**

RFT #: CP1616

ADDENDUM #2
QUESTIONS & ANSWERS

Due Date: ~~May 18, 2016~~ May 19, 2016 before 4:00:00p.m., Local Time
Tender Submission Location: 420 Creek St, Wallaceburg, ON N8A 4C4

Attention of:
Mr. Tony Prizio
Purchasing Department
St. Clair Catholic District School Board

ADDENDUM #2

Information to all proponents:

Alternates

Alternates submitted and approved are found in the attached Table 1, 'Approved Equivalents'. Products failing to meet the performance requirements have not been listed nor approved. Refer to section 16010 1.6 for details on the submission of Alternates

Pricing

Price project based on information contained in Appendix B. Discrepancies found in the drawings will be corrected post award.

Pricing Form

Replace Section 1.2 PRICING FORM on page 9 of bid documents with the attached form 1.2 PRICING FORM (Rev2) and submit with bid.

QUESTIONS (Q) AND ANSWERS (A)

Q 1. Where are the toggle switches that need to be replaced to keyed switches located on the drawings.

A 1. The switches for the corridor lighting are to be replaced with the keyed switches. They are located at the ends of the corridors. They have not been shown on the set of drawings provided. Specific details will be provided to the successful bidder.

Q 2. Which exit signs are to be replaced to LED. They are not marked on the drawings.

A2. Exit signs that are either Incandescent or Compact Fluorescent are being replaced with the new LED exit signs. These have not been shown on the set of drawings provided. Specific details as to the corridor or room location will be provided to the successful bidder. Refer to Appendix B for the quantities in each school to be replaced and to price the job.

Q3. Type V2 to V2 has two different voltages listed.

A3. The retrofit description of Type V2 to V2 in Appendix C describes the 2 lamp ballast required as 347. This is incorrect and the reference should be 120v. The major component referencing the ballast to use is correct as well as the description and quantity in Appendix B. Use the information in Appendix B to price the job.

This concludes addendum #2.

Table - A1

Approved Equivalentents

Note: These approvals are in addition to the representative products already listed in the specifications.

LED LAMPS

4' Lamp "GE - LED18ET8/4/840"
4' Lamp "GE - LED18ET8/G/4/840"
4' Lamp "Philips" 15T8/48-4000 IF DIM 10/1
3' Lamp "GE - LED12ET8/3/840"
3' Lamp "GE - LED11ET8/G/3/840"
3' Lamp "Philips - 12T8/36-4000 IF DIM 10/1"
2' Lamp "GE - LED9ET8/2/840"
2' Lamp "GE - LED9ET8/G/2/840"
2' Lamp "Philips - 8.5T8/24-4000 IF DIM 10/1"
U Lamp "Philips - 16.5T8/22.5-4000 IF-6U 10/1"
MR16 "Cree - MR16-50W-30K-40D"
LED A Lamp - "GE - LED11DA19/827"
BR30 Lamp - "Satco - S9623"
PAR38 Lamp - "Standard - LED/P38/15W/30K/40/STD"

EXTERIOR LED FIXTURES

Wall Pack WP-2 "Rab Design - AWL-LED14W-A-5K-BRZ-PC"
Wall Pack WP-2-347 "Rab Design - AWL-LED14W-C-5K-BRZ-PC"
Wall Pack WP-3 "Rab Design - AWL-LED26W-A-5K-BRZ-PC"
Wall Pack WP-5 "Rab Design - AWL-LED50W-A-KK-BRZ-PC"

Exterior Lighting Retrofit Project

Section 00430

1.2 PRICING FORM (Rev2)

Line No.	School Name and Site No.	(\$ Price 1 Interior, Gymnasium ¹ , Exterior	(\$ Price 2 Corridor Lighting Controls	(\$ Price 3 Corridor Locking Switches	Total Extended Price Per School Price 1+2+3 (\$)
PHASE 1					
1	Christ the King (Site 612)				
2	Georges P Vanier (Site 614)				
3	Our Lady of Fatima (Site 619)				
4	St. Anne - Blenheim (Site 626)				
5	St. Joseph - Tilbury (Site 636)				
6	St. Michael - Ridgetown (Site 640)				
7	Good Shepherd (Site 642)				
8	Ursuline College (Site 725)				
9	TOTAL COST PHASE 1				\$
10	SEPARATE PRICE #1: COST TO BOND PHASE 1				\$
11	HST (PHASE 1)				\$
12	PH1-T TOTAL COST PHASE 1 INCLUDING BONDS AND HST				\$
PHASE 2					
13	Monsignor Uyen (Site 618)				
14	Sacred Heart (Site 622)				
15	St. Anne - Sarnia (Site 627)				
16	St. John Fischer (Site 632)				
17	St. Joseph - Corunna (Site 634)				
18	St. Michael - Brights Grove (639)				
19	St. Peter Canisius (Site 643)				
20	St. Philip (Site 645)				
21	TOTAL COST PHASE 2				\$
22	SEPARATE PRICE #2: COST TO BOND PHASE 2				\$
23	HST (PHASE 2)				\$
24	PH2-T TOTAL COST PHASE 2 INCLUDING BONDS AND HST				\$
25	GRAND TOTAL COST (PH1-T + PH2-T) INCLUDING HST				\$

¹ Include All Sections of Work as outlined in Section 16500, Items 1.4.1 to 1.4.5.